

**ADDENDUM NO. 2  
TO  
CONTRACT DOCUMENTS  
FOR**

**2017 DISTRIBUTION PIPELINE REPLACEMENTS**

**DISTRICT PROJECT NO.: 4035**

**MARCH 17, 2017**

This addendum is hereby attached to and made part of the Contract Documents. The addendum consists of 4 pages of written text (including this cover sheet) and 0 drawing sheets for a total of 4 pages. Each Bidder shall acknowledge receipt of this addendum on the bid and by signing and attaching this addendum to the bid.

**To All Plan holders and/or Prospective Bidders:**

The following changes, additions, and/or deletions are hereby made a part of the 2017 Distribution Pipeline Replacements Contract Documents dated March 2017, as fully and completely as if the same were fully set forth therein:

**Clarification No. 1:**

The District will hire an independent materials testing company to test compaction and density to ensure the Contractor is meeting the District's compaction standards as specified in Section 13.03 of the General Conditions.

**Clarification No. 2:**

For asphalt restoration of all roads, including those in poor condition the Contractor shall be required to install a pavement patch in accordance with the Bid Documents. If the asphalt is unable to hold a clean edge after asphalt cutting the Contractor will not be required to make additional cuts. Any voids beyond the cut shall be filled with asphalt.

**Clarification No. 3:**

The pipeline offset from the edge of curb as specified in the Specifications and Drawings shall not be change at this time.

**Addition No. 1:**

The following addition has been made to SECTION 01020 – MEASUREMENT AND PAYMENT:

- a. Page 2, 101.2, C:

Note: UDOT inspection fees are included in this Bid Item.

**Addition No. 2:**

The following addition has been made to SECTION 02590 – PROTECTION AND RESTORATION OF EXISTING IMPROVEMENTS:

- a. Page 5, 301.03, A, 2:

- j. Work within the UDOT ROW will generally be allowed between 9 am and 3 pm on weekdays. The CONTRACTOR shall be responsible to coordinate with UDOT to verify lane closure restrictions and timing.

**Deletion No. 1:**

The following deletion has been made requiring the Contractor to provide schedule of work in the INFORMATION REQUIRED OF BIDDER:

Page E-3, 13: DELETE bullet point thirteen in its entirety. With this deletion, the Contractor is not required to submit a Proposed Schedule of Work with the Contractor's Bid.

**Revision No. 1:**

**Bids will now be received at 2:00 pm on Tuesday, March 28, 2017** instead of Thursday, March 23, 2017 as indicated on the "Project Cover Page" and the "Receipt of Bids" section of page A-1 of the Contract Documents.

**Revision No. 2:**

The following revisions have been made to the SECTION 01010 - SUMMARY OF WORK:

- a. Page 3, 1.05, B, 1: DELETE first bullet point in its entirety and REPLACE with the following:
  - 1. The CONTRACTOR shall complete all work for the pipeline installation, abandonment, and restoration at 4565 South from 700 East to 785 East by June 30, 2017.

- b. Page 3, 1.05, B, 2: DELETE second bullet point in its entirety and REPLACE with the following:

- 2. The CONTRACTOR shall complete all work for the pipeline installation, abandonment, and restoration at 785 East from 4570 South to 4550 South by June 30, 2017.

**Revision No. 3:**

The following revisions have been made to the SECTION 01020 – MEASUREMENT AND PAYMENT:

- a. Page 6, 101.2, O, 2: DELETE second bullet point in its entirety and REPLACE with:

- 2. Payment Covers: Furnishing all labor, materials, tools, equipment, concrete and landscape removal and restoration, and all incidentals required for the installation of the Copper Water Service Extension to new PVC Pipe – Short Side. A continuous piece of type K copper is required between the new corporation stop and the tie-in location of the existing water service. The connection shall be made with a compression coupler. The distance is measured horizontally from the closest edge of the new C-900 PVC to the existing corporation stop plus 2’.

- b. Page 6, 101.2, P, 2: DELETE second bullet point in its entirety and REPLACE with:

- 2. Payment Covers: Furnishing all labor, materials, tools, equipment, concrete and landscape removal and restoration, and all incidentals required for the installation of the Copper Water Service Extension to New PVC Pipe – Long Side. A continuous piece of type K copper is required between the new corporation stop and the tie-in location of the existing water service. The connection shall be made with a compression coupler. The distance is measured horizontally from the closest edge of the new C-900 PVC to the existing corporation stop plus 2’. This type of extension will typically be used when the new PVC waterline moves to the opposite side of the street causing an existing short side service to be routed across the street and become the new long side service.

- c. Page 10, 101.2, AA, 2: DELETE the sentence “This bid item covers 1/2” SuperPave Mix required by UDOT and SLCo.” and

REPLACE with “This bid item covers 1/2” SuperPave Mix required by UDOT.”

JORDAN VALLEY WATER CONSERVANCY DISTRICT



Kevin Rubow  
Project Manager

**BIDDER'S CERTIFICATE**

I acknowledge receipt of the foregoing Addendum No. 2 and accept all conditions contained therein.

Bidder: \_\_\_\_\_

By: \_\_\_\_\_  
Signature

Date: \_\_\_\_\_