

**ADDENDUM NO 4  
TO  
CONTRACT DOCUMENTS  
FOR  
JORDAN VALLEY WATER TREATMENT PLANT RECLAIM WATER AND SOLIDS  
HANDLING IMPROVEMENTS**

**[DISTRICT PROJECT NO.: 4072]**

**September 8, 2020**

This addendum is hereby attached to and made part of the Contract Documents. The addendum consists of 3 pages of written text (including this cover sheet) and 0 pages of drawings. Each Bidder shall acknowledge receipt of this addendum on the bid (page C-1) and by signing and attaching this addendum to the bid.

Due to widespread power outages in the Salt Lake Valley and business closures on Tuesday, September 8, 2020, the Bid date has been extended to 12 noon on Friday, September 11, 2020. A public bid opening will be held at 8215 South 1300 West in the Board Room. Bidders need not be present.

JORDAN VALLEY WATER CONSERVANCY DISTRICT



David McLean, PE  
Senior Engineer

**BIDDER'S CERTIFICATE**

I acknowledge receipt of the foregoing Addendum No. 4 and accept all conditions contained therein.

Bidder: \_\_\_\_\_

By: \_\_\_\_\_  
Signature


Date: \_\_\_\_\_

**ADDENDUM NO 4  
TO  
CONTRACT DOCUMENTS  
FOR  
JORDAN VALLEY WATER TREATMENT PLANT RECLAIM WATER AND SOLIDS  
HANDLING IMPROVEMENTS**

**[DISTRICT PROJECT NO.: 4072]**

**September 4, 2020**

Digitally signed by Alan M. Domonoske  
Contact Info: Carollo Engineers, Inc.  
Date: 2020.09.08 15:10:03-06'00'



I. CONTRACT DOCUMENTS VOLUME 1: BIDDING DOCUMENTS

A. Document NOTICE INVITING BIDS

1. Page A-4, RECEIPT OF BIDS, REPLACE the bid time and date from "3:00 pm, on Thursday September 10, 2020", as changed in Addendum 3, to "12:00 pm, on Friday September 11, 2020".

II. CONTRACT DOCUMENTS VOLUME 4: DRAWINGS

A. Drawing 1E03 ELECTRICAL ENLARGED SITE PLAN - 2

1. ADD General Note 1 as follow:

"INSTALL ALL CONDUIT AND BOXES OFF THE ROADWAY."

2. ADD a callout for Key Note 5 at three locations: (1) next to the junction tee at sludge lagoon outlet box no. 1, (2) next to the junction tee at sludge lagoon outlet box no. 2, and (3) next to Key Note 4 along the dike/roadway to the Screening Building.

3. ADD Key Note 5 as follows:

"PROVIDE TWO QUARTZITE PULL BOXES, ONE POWER AND ONE FOR SIGNAL."

4. ADD a callout for Key Note 6 next to Key Note 4, and new Key Note 5, along the dike/roadway to the Screening Building.

5. ADD Key Note 6 as follows:

"LOCATE SETS OF PULL BOXES IN THE CONDUIT RUNS BETWEEN LIT-4355 AND THE SCREENING BUILDING BASED ON THE NUMBER OF BENDS AND PULLING TENSIONS."

