

**DOCUMENT 00 90 01  
ADDENDUM #2**

**Project:** 2019-0113

**Date:** Monday, July 17, 2019  
**Bid Date:** Tuesday, July 23, 2019  
**Bid Time:** 2:00 p.m.

---

This addendum shall be considered part of the Contract Document for the above referenced project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall govern and take precedence. Receipt of this addendum shall be acknowledged in the Bid form.

---

**GENERAL INFORMATION**

1. Added a general detail showing configuration of the tremie line around the pump bowls.

**ATTACHMENTS:**

1. Tremie Pipe Detail

**END OF ADDENDUM**

*This page is intentionally left blank.*

**ATTACHMENT #1**

**TREMIE PIPE DETAIL**

INSTALL 940' OF 1 1/2" SCHEDULE 80 FLUSH THREADED PVC CONNECTED W/ STAINLESS STEEL COUPLINGS

INSTALL 1 1/4" SCHEDULE 80 FLUSH THREADED PVC FROM DISCHARGE HEAD TO THE TOP OF THE PUMP ASSEMBLY AS SPECIFIED IN SECTION 22 11 23 OF THE SPECIFICATIONS

ABOVE PUMP BOWLS STRAP PVC TO PUMP COLUMN WITH STAINLESS STEEL STRAPS EVERY 20'

EXISTING 18" WELL CASING

INSTALL PRE-FABRICATED STAINLESS STEEL "GOOSENECK" TO CENTER PVC IN WELL CASING/SCREEN

BELOW PUMP BOWLS INSTALL 1 1/2" X 18" 300 SERIES STAINLESS STEEL ADJUSTABLE CENTRALZERS EVERY 20' PERFORATED PIPE W/ 1/8" DRILL BIT ONCE EVERY 20'. CAP PVC AT BOTTOM

3

## TREMMIE LINE

Scale: NONE