

JORDAN VALLEY WATER CONSERVANCY DISTRICT

6180 SOUTH 3200 WEST SUCTION VAULT UPGRADES

ADDENDUM NO. 1

December 8, 2023

PART 1 – GENERAL

- A. The following ADDENDUM shall be made part of the Contract Documents. The addendum consists of 2 pages of written text (including this cover sheet) and 1 drawing sheet for a total of 3 pages. Receipt of this addendum shall be acknowledged on page C-1 of the Bid Form.
- B. This addendum does not change the bid date. It is still Thursday, December 14, 2023, at 2:00 P.M.

1.1 DOCUMENTS INCLUDE

- A. Answers to questions during the pre-bid site visit.
- B. Clarifications to the project documents.
- C. Changes to the Drawings.

1.2 QUESTIONS

- A. Answers to questions asked during the Pre-Bid Meeting and since then.

- 1. Q: *Can you submit an electronic bid?*

A: Yes, electronic bids or paper bids can be submitted as indicated in the Bidding Documents.

- 2. Q: *Is the Owner supplying the butterfly valves and Victaulic couplings. Can you provide a submittal on the Victaulic couplings.*

A: Yes, the Owner is supplying the two (2) 30-inch butterfly valves and two (2) 30-inch Victaulic couplings. Contractor to provide bolt-kits/gaskets for the butterfly valves. A submittal on the Victaulic couplings and butterfly valves are available to download from the project website at: <https://jvwcd.org/project/1328/6180-s-3200-w-suction-vault-upgrades>

Contractor to transport valves / couplings from Owner's warehouse located at 8215 S 1300 W, to the Site of Work. A forklift is available at the warehouse to load material onto the Contractor's trailer.

- 3. Q: *When is the cut-off date for questions for this project?*

A: Questions will be accepted until 5:00pm on 12/11/2023.

1.3 CLARIFICATIONS

Taylorsville City requested to raise a manhole lid to match the existing asphalt grade. This manhole lid is located within the intersection of 3200 W 6200 S. A supplemental drawing, Sheet C3.0, is added to the Contract Documents via this addendum to identify its location and the added scope of work. Contractor to include the cost to perform this work in Bid Item #3 – Traffic Control/Temporary Markings and Bid Item #6 – New Vault Piping & Appurtenances.

PART 2 - CHANGES

Addendum to include Location and Description of Change:

Item	Location	Description of Change
1	Drawings Sheet C1.1	Modify the notes on Sheet C1.1, Surface Improvements. Modifications listed in red text: 3. CONCRETE CURB & GUTTER AND SIDEWALK REPLACEMENT SHALL CONFORM TO APWA PLANS 205 AND 231. FULL PANEL REPLACEMENT REQUIRED. DOLL-IN #4 EPOXY COATED REBAR ON COLD JOINTS. 4. ASPHALT CUTTING AND PATCHING SHALL MEET TAYLORSVILLE CITY STANDARDS AND CONFORM TO APWA PLAN 255, CURRENT ADDITION. A 2-FOOT OVER CUT AND T-PATCH WILL BE REQUIRED, NO SAW CUT TO END UP WITHIN WHEEL PATH.
2	Drawings Sheet C2.2	Add the following notes to Sheet C2.2: 8. ALL FLANGES SHALL BE AWWA 207 CLASS D. 9. BUTTERFLY VALVES & VICTAULIC COUPLINGS SUPPLIED BY OWNER AND INSTALLED BY CONTRACTOR. STEEL PIPE FABRICATOR TO WELD TYPE D VIC-RINGS TO THE 30" STEEL PIPE SPOOLS PER MANUFACTURER'S RECOMMENDATIONS. 10. CLSM IS REQUIRED FOR PIPE ZONE AND BACKFILL MATERIAL. 11. CONTRACTOR TO SECURE EXCAVATION PIT FROM PEDESTRIAN AND VEHICLE TRAFFIC. JERSEY BARRIERS SHALL BE PROVIDED AROUND OPEN EXCAVATION PIT.
3	Sheet C3.0	Add Sheet C3.0 to the drawing set, see attached.

END OF ADDENDUM

Plot Date: 12/7/2023 3:59 PM
Save Date: 12/7/2023 10:55 AM
By: David Jensen
File: P:\JUVWC0000-0001\0400CAD\VAU\JWCD Suction Vault.dwg

RAISE MANHOLE LID TO MATCH EXISTING ASPHALT GRADE AND INSTALL CONCRETE COLLAR PER CITY'S STANDARD. REINSTALL EXISTING MANHOLE FRAME AND LID

NOTES:

1. MINIMUM ASPHALT THICKNESS IS 6".
2. WORK WITHIN THE INTERSECTION OF 3200 W/6200 S SHOULD BE ANTICIPATED TO BE PERFORMED AT NIGHT AND/OR WEEKENDS. WEEKLY WORK MAY BE APPROVED BY THE CITY BUT THE ROADWAY MUST BE OPEN BY 3 PM ON WEEKDAYS.
3. MINIMUM CONCRETE $f_c=4.0$ KSI. TEMPORARY STEEL PLATES ARE ACCEPTABLE TO ALLOW FOR CONCRETE CURING TIME. CURE CONCRETE PER UDOT SPECIFICATION SECTION 03390.



SITE PLAN
NTS



**DAVID EVANS
AND ASSOCIATES INC.**
10913 SOUTH RIVER
FRONT PARKWAY,
SUITE 150 SOUTH
JORDAN, UT 84095

JVWCD
SUCTION VAULT UPGRADE
JORDAN VALLEY WATER CONSERVANCY DISTRICT
3200 S/6200 W VAULT ACCESS LID
ADJUSTMENT
UT

DATE	DESCRIPTION	BY
12-23	ADDED THIS SHEET	DNUJ ZW

100% SUBMITTAL



11/10/2023

JVWC0000-0001
C3.0